

1 Lift the ceiling tiles upwards

2 How many tiles need to be lifted

The ceiling tiles should be removed as much as the number of sky panels you plan to apply.

Sample 2x3=6 pieces sky panel plan & removed tiles

The specific plan to your choice will be in the product box with the order. This is just an example. You can do the installation by adapting this instruction.

3 Place the panels on T carrier profiles

4 Sky ceiling panels layout and coordinates

- * Sky panels should be placed from left to right and starting from panel 1.
- * Drivers must all be in the same (installers) direction
- * After the placement of the first line is finished, make the electrical connection and then move back to the second line placement.

Note: After making the panel placement for each line, making the electrical connection of that line will provide ease of assembly.

5 Sample backend of panels electricity and image coordinates

The shape of the sky panels visible from below by the observer.

6 Installation steps

- 1- Turn off the electricity
- 2- Remove ceiling tiles as needed
- 3- Place sky panels first line
- 4- Make the electrical connection between the panels on the first line
- 5- If there is more than one line, move backwards and repeat step 3 and 4 for each line, respectively.
- 6- Connect the power cables of the lines to the switch.